जानकी देवी मेमोरियल कॉलेज
(दिल्ली विश्वविद्यालय)
JANKI DEVI MEMORIAL COLLEGE
(University Of Delhi)
सर गंगा राम अस्पताल मार्ग, नई दिल्ली-११००६०
Sir Ganga Ram Hospital Marg, New Delhi-110060
दूरभाष : २५७८७७५४ फैक्स : २५७१०८३२
Tel. : 25787754, Fax : 25710832
E-mail : jdmcollege@hotmail.com, http://jdm.du.ac.in

NAAC Accredited B++

संदर्भ संख्या/Ref. No.....

दिनाँक/Dated 04/Dec/19

Notice Inviting Quotations

Sealed Item rate quotations are invited for works mentioned below from contractors who had executed similar works in PWD/DDA/MCD/NDMC/ Delhi University/any institution/Organization Quotations supported by GST registration no. PAN, TAN, experience certificate, and other relevant documents shall be submitted on letter head of the firm/Company along with the proof of execution of similar works during last 3 years. Contractors/Vendors may visit to the College to see the work/site on any working day from 1000am to 0100pm. Last date of submission of quotation is 18-12-2019 up to 03:00 pm which shall be opened on same day at 03:30pm in the office of Principal Janki Devi Memorial College (JDMC). Quotation received after the last date for whatsoever reason will not be considered. In case of any dispute (S) the decision of the undersigned will be final and binding. The Undersigned reserves the right to reject all the quotations or any one full or in part without assigning any reason thereof.

Name of Work-Quotation for Retrofitting work at slab at JDMC.

Scopes of work are as follows:-

Quotation for Retrofitting Work at slab					
S.no	**Description**	**Qty**	**Unit**	**Rate**	**Amount**
1	Chipping of existing cement plaster manually from masonry or concrete surface using chisel and hammer disposal of debris within a lead 50m complete.	30	Sqm		
2	12mm cement plaster of mix:	as reqd	Sqm		
2.a	1:1:2 (1cement:1coarse sand :2fine sand)	30	Sqm		
3	Providing & application of bond coat on the concrete surface by maxing high dispersion SBR latex like Master Emco SBR 2 of BASF with white cement in the ratio of 2:3 the mixing should be done to a lump free consistency for the bond coat and the screed/mortar should be applied & once the bond coat is tacky Master Emco SBR 2 of BASF or Nittobond SBR-2 (Latex) of Fosroc or Equivalent.	30	Sqm		
4	Cleaning reinforcement of total rust by tapping & using mechanical wire brush of any other suitable way including from behind and around the reinforcement bars to give it totally rust free finished bars to give it totally rust free finished steel surface. Rebacling primer SB-R equivalent (mode of measurement.)	20	Sqm		

5	Providing & supplying the one component, Polymer modified cementitious anti corrosion primer (having the technical parameters mentioned in material Specification) formulated to provide dual protection of a polymeric barrier and an integral corrosion inhibiting system to the existing steel and additional system steel provided before patching of damaged areas, using suitable tools and Equipment inclusive of material manpower and equipment BASF Master Emaco P 130/Fosroc Nito prime Zinc rich/Sika Rust off 100 or other equivalent.	20	Sqm		
6	Disposal of excess earth/building rubbish/malba/similar un service able dismantled or waste materials by mechanical means including loading transporting unloading to approve by engineer-in-charge, beyond 50m initial lead, for all lead including all lifts involved.	03	Trip		
7	Providing and fixing double scaffolding system (cup lock type) on the exterior side up to seven store height made with 40mm dia m.s tube 1.5m centre to centre horizontal and vertical tube joining with cup & lock system with m.s tube challises, m.s clamps and m.s stair case system in the scaffolding for working platform etc and maintaining it in a serviceable condition for the required duration as approved and removing it thereafter as per direction of Engineer-in charge.	20	Sqm		
8	Providing and using single component cement based non-shrink micro concrete of approved manufacture by mixing graded stone aggregate 10mm and down and coarse sand as per manufactures specification & direction of Engineer in charge complete as per design and approved by Engineer in charge at all floor and all heights.	25	Sqm		
9	Providing making fixing & anchoring of reinforcing bars or dowels or rebar including drilling the holes, fixing the bar and grout the bar with Hilty HIT –HY-150 grouting chemical, all labour all tool & plant necessary scaffolding etc but excluding the reinforcement steel complete for all lead & lift as directed by engineer Incharge/structural consultants or Architect, Rebarring depth minimum 300 or 20 D whichever is more.	as reqd			
9a	10mm dia	80	Nos		
9b	12mm dia	80	Nos		
10	Steel reinforcement of RCC work including straightening, cutting banding solacing in position and binding all complete up to all level.				
10a	Thermo-Mechanically Treated bar	50	Kg		

NOTE: - APPLICABE G.S.T 18% EXTRA.

प्राचार्या/Principal
जानकी देवी मेमोरियल महाविद्यालय
Janki Devi Memorial College
सर गंगा राम हॉस्पिटल मार्ग नई दिल्ली–110060
Sir Ganga Ram Hospital Marg, New Delhi-110060

Terms & Conditions

1. Work shall be done as per latest CPWD specification 2014 with up to date Corrections Slips and direction of Engineer/Architect/Site in – charge.
2. Water and electricity shall be supplied by College and recovery @ 1 % for water and 1 % for electricity shall be made from dues of contractor.
3. 10 % of the cost shall be retained as security deposit and shall be released after one year of defect liability period.
4. Work is to be completed within 30 days from date of issue of letter (work order) otherwise compensation @ 1 % (One per cent) of Cost of work per day subject to maximum of 10% of cost of work shall be recovered from contractor's bill.
5. TDS for Income Tax & labor cess shall be deducted as per govt. rules from dues/bill of the contractor.
6. Rates shall be inclusive of all Taxes including GST, Octrio, Cartages, loading, unloading etc. nothing extra is payable.
7. Rate quoted shall be including of GST, as applicable. Any changes/revision of Rate in Taxes made by Govt. after award of work shall be adjusted upward or downward, as the case may be.
8. Sample of all Material/Item/Equipment shall be got approved before use by engineer/architect/competent authority.
9. Decision of Principal JDMC shall be final and binding in case of any dispute or interpretation of description of item in B.O.Q/Specification of work or any other criterion. College is not bound to give work to L1.
10. Site shall be handed over in neat and clean condition after removing all Malba/Surplus Material/Site Stores/Jhuggi/Hutments etc. Contractor will inform in writing about completion of work.

Swati Pal.

Dr. Swati Pal
Principal